



888 258 1445

P.O. Box 1083 Willamina, OR 97396
www.futureforestry.com
contact@futureforestry.com

HUGO

Unpacking & Assembly

*The Hugo is a large and heavy structure. Please insure that there are enough hands to handle it safely.
For this one-time assembly, we recommend three people.*

Unpacking of the Shipping Pallet

1. Strip away all plastic wrap
2. Remove small parts (including tires) by cutting straps holding those parts
3. Carefully remove drop-tongue while cutting straps (large diagonal piece)
4. Lower drop tongue and lay-out all parts
5. On Main Arch, notice long and short end and where small parts are attached to chains
6. Before installing tires on Main Arch hubs, install drop-tongue in the short end of the arch
7. At this point, the Arch will be stable, and steel shipping structure can be removed

Assembly

In most cases, and for the (optional) brakes to work; the long end of the arch should be forward

1. With structure short-coupled as in Unpacking Instructions, install tires
2. Install Reach and pins in long end of the Arch
3. With help, remove Drop-Tongue from short end and install into reach (configuration for carrying longest logs)
4. Install pins, battery boxes (optional), winch (optional), and string Hand-Winch line back through the smaller of the two blocks on rear chains
5. Install Light Bar (optional), Trailer Brake wiring (optional), and charging system (optional)